

# Calmar Manufacturing Company, Inc. 402 E. Main • P.O. Box 250 Calmar, Iowa 52132

Subsidiary of Imperial Woodworking Co.



April 15, 2021 / Revised 4/19/21

Mr. Andy Riha Andy's Cabinet Shop 211 North Gilmore Ave. New Hampton, IA 50659

Project Name:

**New Hampton Elementary Classrooms** 

New Hampton, IA

Dear Mr. Riha:

Per your request and in accordance with drawings received by email dated 3/29/21, we submit our bid proposal as follows:

Specification #CMC

Our Base Quotation excluding tax is for the sum of:

Option #1: (2) Classrooms @ \$5,925 Each	Add	\$11,850
Option #2: (18) Classrooms @ \$2,625 Each	Add	\$47,250
	Total	\$59,100

NOTE: If (10) Rooms or Less are Taken add 3% to Room Total

Freight (1) Semi-Truck Delivery:	Add	\$300
----------------------------------	-----	-------

Production is quoted for July 2021.

Sincerely,

Calmar Manufacturing Co., Inc.

Subsidiary of

Imperial Woodworking Company

Jeff Martin, Senior Estimator

# New Hampton Elementary Classrooms April 19, 2021

### **OPTION #1 INCLUSIONS: PER CLASSROOM**

- 1. (1) 1-door/1-drawer base cabinet 16" wide.
- 2. (1) 2-door sink base cabinet with apron 32" wide.
- 3. (4) 4-drawer base cabinets 36" wide.
- 4. (2) 1-door tall cabinets 16" wide with 1-fixed and 4-adjustable shelves.
- 5. (2) 2-door tall cabinets 32" wide with 3-pullout shelves, 1-fixed shelf and 1-adjustable shelf.
- 6. Plastic laminate countertop with back splash.

## **OPTION #2 INCLUSIONS: PER CLASSROOM**

- 1. (2) 2-door/1-drawer base cabinets 30" wide.
- 2. (1) 2-door sink base cabinet with apron 36" wide.
- 3. (2) 4-drawer base cabinets 27" wide.
- 4. Plastic laminate countertop with back splash.

#### NOTE:

1. Plastic laminate based on Formica -58 series colors or Wilsonart -38 or -60 series colors.

## The Following Casework Construction Features Apply:

- 1. Overlay Construction
- 2. (45#) NAUF Particleboard Substrate
- 3. GP28 Plastic Laminate for Exposed Surfaces
- 4. Low Pressure Melamine Overlay for Semi-Exposed Surfaces
- 5. 3mm PVC Edging (for Door & Drawer Fronts)
- 6. .020 PVC Edging (for Cabinet Bodies)
- 7. .020 PVC Edging (for Shelving)
- 8. Base: Assembled Exterior Grade Plywood
- 9. Casework Assembly: Concealed mechanical fasteners
- 10. Drawer Box Assembly: Dovetailed Construction
- 11. Low Pressure Melamine on 1/2" MDF for Drawer Sides
- 12. Drilled Holes for Shelf Support
- 13. 5-Knuckle Institutional Hinges
- 14. Accuride 3832 Drawer Slides
- 15. Wire Pulls
- 16. Self-Edged Countertops with top applied back and side splashes

#### **EXCLUSIONS:**

- 1. Field measurements.
- 2. Installation.
- 3. In-wall blocking.
- 4. Sinks and fixtures.
- 5. Standing and running trim.
- 6. Tackboard, markerboard, chalkboard.
- 7. Applicable Taxes.