

Bob Ayers

Office of Superintendent
New Hampton, IA



Dear Bob,

4-30-15

I've enclosed several Asphalt Maintenance Proposals for the High School and Elementary School Lots that You, John & I walked on good Friday.

(page #1 & #3) The 4" Asphalt Patching & 3" Asphalt Patching areas would have to be done first, prior to any Asphalt Slurry Sealing Proposals or any 2" or 2 1/2" Asphalt Overlay Proposals. (The 4" & 3" Asphalt Patching/core-outs are needed to make lots ready for sealers or Overlays)

The Asphalt Slurry Sealer & Crack-Filling Proposals employ the same process & result as last year's Rec Trail Project - sealed in 2014!

Please Call with any questions or would like to walk thru any Proposals.

Thanks,

Mark Steffes
#319-404-7770

ATTN: Bob Ayers
page #1



16 North Taft Street
 PO Box 632 • Humboldt, IA 50548
 (515)332-4208 office • (515)332-3653 fax

New Hampton
 Community School District
 New Hampton, IA

No.	Street	Type of Work	From	To	Size	Sq. Yards	Patch	Cost
	Fitness Center	4" Asphalt	Broken, Cracked & loose areas		31x18	entrance area		#3,063. ⁴²
		Patching,	@ Fitness Center lot		18x5	rear		#494. ¹⁰
		Milling &			30x6	rear		#988. ³⁰
		excavation			10x10	@ drain		#549. ⁰⁰
	Upper Level	Tack Coat	Upper Level Lot		7x7, 3x3	NW(R) & entrance		#318. ⁴²
		"			15x6	- south edge		#494. ¹⁰
		"			25x4, 10x6	- south edge		#878. ⁴⁰
		"	<u>Optional NE (R) between entrances</u>		30x14	area between upper/lower levels entrance		#2,305. ⁸⁰
	Lower Level	"	Main Road area & Intersection		13x14	Intersection		#999. ¹⁸
		"	@ Fitness Center		42x13	main Road @ Int		#2,997. ⁵⁴
		"			9x10	" " & north		#494. ¹⁰
		"			9x9	" "		#444. ⁶⁹
		"			10x7	" "		#384. ³⁰
		"			10x7	" "		#384. ³⁰
	Lower level	Asphalt Patching	Approx 5 or 6 small pot-holes @					#395. ⁰⁰
			clean, Tack & Fill with Hot Asphalt Patch					#
<u>Total Project Cost =</u>								<u>15,190.⁵⁵</u>

Measured by: Mark J. Steffen #319-404-7770

Accepted by: _____

Date: 4-28-15

Date: _____

ATTN: Bob Ayers
Page #3



16 North Taft Street
 PO Box 632 • Humboldt, IA 50548
 (515)332-4208 office • (515)332-3653 fax

New Hampton
 Community School District
 New Hampton, IA

No.	Street	Type of Work	From	To	Size	Sq. Yards	Patch	Cost
Elementary School		4" Asphalt Patching, Milling & Excavation, Tack Coat	Broken, cracked & loose areas @ Elementary School		38x22			\$4,589. ⁰⁴
					20x9			\$988. ³⁰
			Areas south of Garbage Dumpsters		40x10			\$3,196. ⁰⁰
					20x9			\$988. ³⁰
					30x8			\$1,317. ⁶⁰
		3" Asphalt & 2" Milling & Tack Coat	low-area, south @ BB Courts	between	15x7			\$499. ⁸⁰
			@ north side of BB Courts		30x7			\$999. ⁶⁰
			Low - Bumps					
Elementary School Total Patching Cost =								\$11,579. ⁰⁴
High School lower level Main Road & Int.		2 1/2" Asphalt Overlay, Patching & Tack Coat	Entire Intersection Center, then north Main lot = Main Road	@ Fitness	19x47, 44x55		Raise 1 Man-Hole & 1 Water Valve	
					1/2 @ 19x19, 20x4			
			PREP: Clean, 10 Tons Asphalt		36x30		Covers low area @ Main lot (puddle)	
			patch leveling, Tack & 2 1/2" Overlay					
High School Main Road & Intersection Total Cost =								\$20,970. ⁰⁰

Measured by: Mark G. Steffen
 Accepted by: _____

Date: 4-29-15
 Date: _____


ATTN: Bob Ayers
 #319-830-1566

page #3



New Hampton
 Community School District
 New Hampton, IA

No.	Street	Type of Work	From	To	Size	Sq. Yards	Patch	Cost
#1 Option	Fitness	Asphalt	Entire Asphalt Parking Lot		53x130			
	Center	Slurry	Clean lot & blow-out		28x16, 31x51			
	Lot	Seal & Crack-Filling	cracks, prior to Asphalt		41.5x44			
			Slurry Sealer entire lot,		68x26.5			
			and Fill cracks with		80x45, 23x5			
			Rubberized Hot-Melt Asphalt		26x24			
		Sealer	cracks @ 888' L.F.	38x60				
#1 Option @ Lot Sealer & cracks Filled/Total Cost = \$5,980.								
#2	Fitness	2" Asphalt	Entire Asphalt Parking Lot		53x130			
	Center	Overlay,	Clean lot, Apply 10 Tons, Patch/		28x16, 31x51			
	Lot	Patching & Tack Coat	leveling prior to 2" Asphalt		41.5x44			
			Overlay. Mill perimeter		68x26.5			
			prior along e.g.		80x45, 23x5			
					26x24, 38x60			
#2 Option @ 2" Asphalt Overlay Total Cost = \$24,880.								



Measured by: Mark J. Steffer #319-404-7770
 Accepted by: _____

Date: 4-29-15
 Date: _____

ATTN: Bob Ayers

page #4



New Hampton
Community School District
New Hampton, IA

No.	Street	Type of Work	From	To	Size	Sq. Yards	Patch	Cost
(#1) ↑	Upper	Asphalt	High School Upper Level - entire		408x35			
	Level	Slurry	Asphalt Lot Area		94x34			
	Lot	Seal &	Clean lot & Blow-out all		98x35			
		Crack-	cracks prior to liquid		28x19			
		Filling	Asphalt Slurry Sealer applied.		14x20@55%			
			649' L.F. of cracks will be		17x8@50%			
			Filled with Rubberized Asphalt					
			Hot Melt Sealer.					
(#1) Option with Lot Sealer & cracks Filled								Cost = \$ 00 <u>5,895.</u>
OR ↓ (#2)	Upper	2" Asphalt	High School Upper Level lot		408x35			
	Level	Overlay,	Clean, Mill perimeter edge		94x34			
	Lot	Tack Coat	along agg, Tack & 2" Asphalt		98x35			
			overlay entire lot.		28x19 14x20@55%			
					17x8@50%			
(#2) Option @ 2" Asphalt Overlay Total Cost =								\$ 00 <u>26,940.</u>

Measured by: Mark J. Steffer #319-404-7770

Date: 4-29-15

Accepted by: _____

Date: _____

ATTN: Bob Ayers

page #5



16 North Taft Street
PO Box 632 • Humboldt, IA 50548
(515)332-4208 office • (515)332-3653 fax

New Hampton
Community School District
New Hampton, IA

No.	Street	Type of Work	From	To	Size	Sq. Yards	Patch	Cost
	Elementary School	Asphalt Slurry	Elementary School lot @		106x65,			
		Sealer & Crack-Filling	Entire Asphalt Area		43x34, 188x165			
					70x25, 54x22			
			<u>PREP:</u> Clean entire lot &		40x13, 11x22			
			<u>Blow-out</u> all cracks,		42x34, 40x80			
			Apply Liquid Asphalt Slurry		50x59, 30x18, 36x26			
			Sealer to entire area. Fill					
			all <u>3,545'</u> L.F. of cracks					
								\$ <u>16,869.⁰⁰</u>
								Above Project Total Cost =

Measured by: Mark J. Steffen #319-404-7770

Date: 4-29-15

Accepted by: _____

Date: _____