



2303 150<sup>th</sup> Street

New Hampton, Iowa 50659

Phone: (319) 240-6077 \* Fax: (641) 394-4769

Estimate For: New Hampton Community Schools John's Phone #:641-330-5978

Date:10/24/19

Includes:

- 40'x 72' with 12' sidewalls
- Wood post frame columns
- 2x6 sidewalls
- Rafters 4' on center
- 2x4s flat
- 2' overhang
- 1, 18' x 10' Overhead door with operator
- 2, Walk doors
- 3, Windows
- 10' x 10' awning on corner
- Colors to be determined by owner
- Electrical
- Plumbing and water to be stubbed out
- Heat
- 4' frost walls and footings
- Excavation
- Back fill, fill materials
- Foam under floor
- 5" reinforced floor
- Post column brackets placed in concrete
- Power trowel smooth finish floor
- 1 drain

Total: \$99,850

*Estimate is good for 10 days*

*Please sign and return one copy to accept estimate*

Accepted By: \_\_\_\_\_

Submitted By L&C Builders

Date: \_\_\_\_\_

By: \_\_\_\_\_

Dennis Steinlage

**Terms and conditions:**

30% down payment      50% when materials are delivered      20% when project is completed