

Customer: New Hampton High School Date: April 20, 2016

Address: Bob Ayers

710 W. Main St

New Hampton, IA 50659

Phone: 641-394-2134

Cell: 319-830-1566

Area(s): 2 Kitchen Coolers @ 324 sq ft

**Job Description:** Prep existing floor by grinding. Install a quartz epoxy system with a urethane top-coat.

## **Scope of Work:**

- 1. Prep floor by diamond grinding for proper coating adhesion.
- 2. Prep surfaces by shot blasting and diamond grinding top for profile.
- 3. Patch and fill any *major voids* as needed.
- 4. Apply full quartz epoxy system with long-wear urethane top-coat in color of customers preference.
- 5. Clean up any debris or garbage.
- Men's Locker-room: Apply full flake epoxy system with long-wear urethane top-coat. In color of customer's preference. 324 square ft @ \$2,916.00

Project Total with full Quartz system: @ \$2,916.00

Buff and Re-coat the two bathrooms during this time as well.

- Customer to provide power and dumpster for waste.
- Working area must be clean and dry prior to HTF arrival.

• Temperature must be a minimum of 60 degrees Fahrenheit.

## **ACCEPTANCE OF TERMS:**

Terms and conditions of this contract only take place when both parties have agreed to scope of work and price. Negotiation may take place if scope or price is indifferent. We ask that the customer give as much information about their facility as possible to make accurate decisions in putting the best possible system down in your facility. HTF Solutions, LLC sales representative, and Job Foreman will evaluate every floor, wall, or pipe prior to installation for proper structural conditions. Some aspects of the floor may not be initially detectable, such as deeper concrete issues. If for any reason HTF encounters an unknown problem with the structure of the walls, floors, or pipes, they may increase the price or terminate the project with the owner's approval and acknowledgement of termination.

TERMS OF PAYMENT
If applicable 30% down before job commenceN/A
Payment in full of each invoice is due and payable within (30) days of completion of b. (NET 30) Any payment which remains unpaid after such (30) day period, and hich is not being held pending resolution of any dispute, shall bear interest from the atte such payment is due at the annual percentage rate (APR) of 18 percent (18%) per anum. If price or performance of work is under dispute HTF Solutions shall be paid a corated rate or have the ability to satisfy each customers complaints. If satisfaction does not occur between both parties a mediator may be brought in to solve the problem, such a product representative.  WARRANTY
HTF Solutions, LLC warrants that all floor materials applied by HTF Solutions, LLC ill not peel or lose bond due to improper preparation and application. Epoxy and rethane coatings and resurfaces are covered for a warranty period of (36) months, cluding the cost of labor and materials; provided, however, that when applying a sealer coating over previously or coated surfaces, HTF Solutions, LLC warrants only a bond the existing surface and assumes no responsibility for the bond between the floor and e previous sealer or coating. NO WARRANTY IS MADE FOR APPLICATION THERE SUBSTRATUM FAILURE OR, HYDROSTATIC PRESSURE OCCURRS.
, or it's representative, hereby understands and eknowledges the terms and conditions of this contractual agreement.
ame, Position:
gnature:Date:
TF Solutions, LLC:
uentin Tranberg
n. 651-558-1862