

Estimate
D. Randall Construction, L.L.C.
2010 357th St
Osage IA 50461-8346
641-732-4258

02/14/2019

New Hampton Schools
1913 Elementary School Building

South Side Gable:

- Remove brick and stone
- Remove roof framing and change to match existing roof
- Fix any masonry relating to changes
- Gutters?

West Side Gable:

- Remove brick and stone to below roof line
- Frame roof over masonry wall
- Cover fascia with metal
- Put temporary roofing paper on
- Fix any masonry relating to change

East Side Gables:

- Remove & relay stones that are bad
- May need to replace stones
- Repair masonry wall under stones
- Properly clean up wall under work area

Remove Large Louver Off Center of Peak

- Remove Louver
- Rebuild roof framing to enclose opening
- Temporary paper roof

Note:

- Northern Cedar Service to do shingling
- All work areas will be secured and properly cleaned up at completion of job

This estimate includes all material, labor, and equipment to complete job as described. There is always a possibility on a 100-year building some unexpected things will come up. If something should arise, we will contact the schools building representative to talk about a solution. Randall Construction works to keep everyone on the same page.

Thanks for the opportunity to estimate this work.

Estimate to complete this work as described: **\$85,800.00**

Please call if you have any questions.

THANK YOU

Dave Randall