



Customer: New Hampton Schools

Date: March 10th, 2013

Address: Bob Ayers
701 W. Main ST
New Hampton, IA 50659

Area(s): Hallways, Commons Area, Classroom

Job Description: Remove existing floor covering and install a full-flake epoxy system with a urethane top-coat.

Scope of Work:

1. Remove existing floor covering.
 2. Prep surfaces by shot blasting and diamond grinding top for profile.
 3. Patch and fill any *major voids* as needed.
 4. Apply full flake epoxy system with long-wear urethane top-coat in color of customers preference.
 5. Clean up any debris or garbage.
- Hallways: Apply full flake epoxy system with long-wear urethane top-coat. In color of customer's preference. 5228 square ft @ \$22,219
 - Commons Area: Apply full flake epoxy system with long-wear urethane top-coat. In color of customer's preference. 1668 square ft @ \$7089.00
 - Classroom: Apply full flake epoxy system with long-wear urethane top-coat. In color of customer's preference. 1,170 square ft @ \$4,972.50

A water-based primer is recommended and may be required for an additional \$.40 cents per square foot.

Project Total with options @ \$34,280.50